

TVRFP Riser

vertical high rise riser

Factory assembled or shipped loose risers are pressure tested before shipping. Ship loose riser offers flexibility in terms of installation and keeps the units away from the construction debris during riser testing and installation minimizing the damage.



Features and Benefits

- Type M or L copper with swaged connections
- 3/4" to 3" diameters and 100" to 120" length available
- 1/2" and 3/4" closed cell insulation
- Type M copper condensate/Drain Riser
- Riser extensions, caps and covers available
- Ship in advance risers

