



Submittal

DEDV

Dual Duct Terminal Unit





Inlet Size	CFM Range	Α	D	F	G	Н	L	М	W
4	0-225	12 ¹ / ₈	3 ⁷ / ₈	2 ¹ / ₈	7 ³ / ₈	8	15 ¹ / ₂	5 ³ / ₈	24 ¹ / ₈
5	0-350	12 ¹ / ₈	4 ⁷ / ₈	2 ¹ / ₈	7 ³ / ₈	8	15 ¹ / ₂	5 ³ / ₈	24 ¹ / ₈
6	0-500	12 ¹ / ₈	5 ⁷ / ₈	2 ¹ / ₈	7 ³ / ₈	8	15 ¹ / ₂	3 ³ / ₈	24 ¹ / ₈
7	0-650	12 ¹ / ₈	6 ⁷ / ₈	1 ¹ / ₈	7 ³ / ₈	10	15 ¹ / ₂	3 ³ / ₈	24 ¹ / ₈
8	0-900	12 ¹ / ₈	7 ⁷ / ₈	1 ¹ / ₈	7 ³ / ₈	10	15 ¹ / ₂	3 ³ / ₈	24 ¹ / ₈
9	0-1050	14 ¹ / ₈	8 ⁷ / ₈	-	5 ³ / ₈	12 ¹ / ₂	15 ¹ / ₂	3 ³ / ₈	28 ¹ / ₈
10	0-1400	14 ¹ / ₈	9 ⁷ / ₈	-	5 ³ / ₈	12 ¹ / ₂	15 ¹ / ₂	3 ³ / ₈	28 ¹ / ₈
12	0-2000	16 ¹ / ₈	11 ⁷ / ₈	-	5 ³ / ₈	15	15 ¹ / ₂	3 ³ / ₈	32 ¹ / ₈
14	0-3000	20 ¹ / ₈	13 ⁷ / ₈	-	3 ³ / ₈	17 ¹ / ₂	15 ¹ / ₂	3 ³ / ₈	40 ¹ / ₈
16	0-4000	24 ¹ / ₈	15 ⁷ / ₈	-	3 ³ / ₈	18	15 ¹ / ₂	3 ³ / ₈	48 ¹ / ₈
1									

Accessories (Optional)

Accessories (Optional)									
Check	if provided.								
	24V Control Transformer		SteriLoc Liner		Dust Tight Enclosure Seal				
	Disconnect Switch		1" Fiberglass Liner						
	Fibre Free Liner		Hanger Brackets						

General Description

- Standard construction is 22 gauge steel housing with 20 gauge construction as optional. Mechanically sealed and gasketed, leak resistant construction. Less than 2% of nominal cfm at 1.5" sp wg.
- Dual density internal insulation, treated to resist air erosion.
 Meets requirements of NFPA 90A and UL 181.
- Multipoint center averaging inlet velocity sensor.
- Direct digital control package supplied by Titus includes direct digital controller, damper actuators, and flow transducers (all tested and calibrated.) Room sensor is optional.
- Direct digital control package can be factory mounted by Titus from various manufacturers. Consult your Titus representative for availability.
- Gauge tees for cfm measurement.
- Choice of right hand or left hand cold duct location. Right hand is standard.
- Rectangular discharge opening is designed for slip and drive cleat duct connection.